BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Modified Schedule-B

NAME OF WORK: Modified Schedule-B for UGD Maintanance at Kirloskar Layout, NMH Layout & Sahyadri layout in Bagalagunte Ward No.14

Sl. No	Description of work	Unit	Qty	Modified approved rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earth work Excavation for foundation of Buildings, water supply, sanitory lines and electrical conduits either in pits or in trenches 1.5m and above in width. In Hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50m after breaking of clods complete as per specification	Cum	506.41	285.00	Rupees Two Hundred Eighty Five Only
2	Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure of outside diameter raising mains & exposed distribution pipes with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM and testing complete as per specifications. 75MM dia	Mtr	450.00	404.00	Rupees Four Hundred Four Only
3	Providing and laying in position to required level or slope 300mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications.	Mtr	130.00	628.00	Rupees Six Hundred Twenty Eight Only

Signature of the Contractor,

Executive Engineer
Dasarahalli Division

Scanned with CamScanner

4	Constructing brick masonry circular type manhole 1.67m internal dia at bottom 1.67 m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3,finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsixe granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming IS : 12592, total weight cover and frame to be not less than 182 Kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machinery, completete as per specifications.(Excavation, footrests and 12mm thick cement plaster on the	Each ~~Mtr~~	13.00	21273.00	Rupees Twenty One Thousand Two Hundred Seventy Three Only
5	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Cum	18.53	6732.00	Rupees Six Thousand Seven Hundred Thirty Two Only
6	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	Sqm	51.60	236.00	Rupees Two Hundred Thirty Six Only
7	Providing & Fixing SFRC Cover and frame 560mm (ID) Heavy Duty.	No	13.00	906.00	Rupees Nine Hundred Six Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division.

Scanned with CamScanner

	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour complete as specifications.. allow 60% of rate considered under item	Cum	506.41	77.00	Rupees Seventy Seven Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials asAdd loading and unloading	Cum	303.85	66.00	Rupees Sixty Six Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned with CamScanner